

Orange & Rockland

# **Tuxedo Park - 4kV conversion**

May 20, 2019

### **Agenda**

- Overview
- Existing Conditions
- Proposed Upgrade
- Construction Impacts
- Example Photographs
- Example Installation

#### **Overview**

- Tuxedo Park serves a total of about 418 customers
- This project area serves 270 residential customers, the Tuxedo Park School, Tuxedo Park Country Club, Tuxedo Park DPW and Sewer Plant, and a Verizon Communication Switching Station
- Load growth from customer service upgrades
- First of four major projects to upgrade the main line overhead distribution system and increase reliability

### **Existing Conditions**

- Original system
- Majority of the Village is fed by 2.4kV open wire overhead primary
- Aging infrastructure and overloaded conductors
- Susceptible to tree outages
- Low voltage conditions during peak periods

### **Proposed Upgrade**

- Upgrade to 13.2kV Hendrix overhead distribution
- Install step down transformers to service side spurs
- Replacement of approximately 15,000 feet of existing overhead conductor with higher capacity mainline spacer cable (Hendrix)
- Installation of 7 MOABs and 2 GOABs to assist is isolation and restoration

## **Construction Impact**

- Material Storage
  - 94 poles
  - 5 Reels Hendrix cable
  - Secondary conductor reels
  - Pole mounted transformers and step banks
  - Cross-arms
  - Connectors, lighting arrestors, bushings, brackets, etc.
  - Dumpsters
- Tree Trimming
  - Majority of new poles are 45' or 50' to meet construction standards

#### **Roads affected**

- Continental Drive
- We-Wah Road
- Continental Road
- West Lake Road
- Clubhouse Road
- Turtle Point Road
- Lake Road

- Tower Hill Road
- Laurel Road
- Circuit Road
- Lorillard Road
- Ontio Road
- Summit Road
- Mountain Farm Road

## **Construction Impact**

Approximately 6-9 month duration

Double wood condition where telephone and cable have to

transfer facilities to new poles

Contractor will remove double wood after transfer



### **Construction Impacts**

- Bucket Trucks
- Digger Derricks
- Movement of equipment and materials





# **Example Photographs**



Pole Delivery



Pole Storage



Pole transport example 1



Pole transport example 2

# **Example Installation**

New Hendrix Spacer Cable

Secondary circuit (services)

Cable/Telephone to be transferred

Double Wood

